



Metano Ltd

Unit 14/15 Whinfield Way, Whinfield Industrial Estate,
Rowlands Gill, Tyne & Wear, NE39 1EH, UK
Tel: +44 (0) 1207 549448 Fax: +44 (0) 1207 549447

Metercube IBC Manlid Swing Bolt Tightening Procedure

1. Ensure manlid is positioned centrally over the neckring
2. Tighten swingbolts in number order as shown in the sketch below to a torque setting of 15Nm
3. Repeat operation 2 at intervals of 10 minutes until when revisiting the swing bolts click off immediately at 15Nm
4. After a further 10 minutes finally tighten to a torque setting of 20Nm in number sequence as shown below

